



THINGS YOU SHOULD KNOW PRIOR TO FIELD ENGINEERING / TEMPLATE:

Cabinets and areas to be measured must be leveled & fully installed including finished panels, sheet rock, etc. prior to field engineering. Nothing should be added AFTER field engineering has occurred, as this will cause the countertops to not fit properly.

- We require a decision maker over the age of 18 to be on-site to review items such as overhangs, radius corners, tub decks, showers and outdoor areas along with questions that arise during the Field Engineering process. If not, this can delay your project.

- Sinks, faucets, cooktops must be on site. (in some instances, model #s are not enough information to engineer your project.)

- FARM / APRON front sinks MUST BE INSTALLED prior to field engineer date.

- Existing countertops should be CLEARED of items.

- If there is full height backsplash, a conversation is required prior to upper cabinets being installed and or a decision made on the best way to make them fit properly.

- It is the customer's responsibility (unless purchased at Smokey Mountain Tops) to make sure that sinks, cooktops and faucets fit into the base cabinet, (for example: 42" sinks will not fit into a 30" sink base).

PLEASE NOTE: *To avoid return trip charges, please confirm that all base cabinets & countertop-related carpentry are completed PRIOR to final field engineering or a \$125.00 charge will be incurred for return trips to the job site.